

PRE-BID CLARIFICATIONS - Tender No.CME/PROJ/METERING/2016/3.

PRE BID MEETING HELD ON 12.05.2016 AT 1130 HRS OF “SUPPLY, INSTALLATION, TESTING AND COMMISSIONING OF 33 KV METERING CUBICLES, TRI-VECTOR METER, INCLUDING STRUCTURES AND ACCESSORIES AT 33 KV S/S, MPT”

Sr. no	Reference No in the tender	Page No.	Queries / Comments & Suggestions with relevant reasons / remarks	Port's Clarification
1.	Clause 2.8	21	The cost towards fees payable towards Electrical Inspector	The contractor shall arrange the CEI for carrying out inspection of the proposed installation, payment of the related fees will be to the contractor's account. However, the Contractor shall obtain Port's prior approval on the related documentation.
2	----	----	The cost towards Supervision charges payable to the Electricity Dept, GoG.	Supervision charges payable to the Electricity Dept, GoG would be payable by the Port. However, liasoning with the Electricity Dept. would have to be done by the contractor.
3	Clause 1.10	9	Bid validity period from 180 days to 120 days in view of continuous price rise.	Bid validity is changed to 120 days from 180 days
4	Clause 2.1, Sr. No. 7	19	Add make PACTIL and ATLAS for Isolator/ AB Switch.	Makes, PACTIL and ATLAS are added to the existing 1. GR SWITCH GEAR LTD., 2. ULTIMA SWITCH GEAR, 3. S&S SWITCH GEAR for Isolator/ AB Switch
5	Clause 2.1, Sr. no. 4 & 5	18	The type of CTs and PTs be changed from Oil immersed to Resin Cast for accommodating the same within the metering cubicles.	The type of CTs and PTs is changed from Oil immersed to Resin Cast.
6	Clause 2.2	20	General	Port intends to include a control panel and 33KV breaker in the circuit during Phase-II of this work The Contractor is required to make the necessary provisions in the scheme during the present work.