

**BILL OF QUANTITIES  
FINANCIAL BID**

**MAINTENANCE DREDGING AT MORMUGAO PORT FOR THE YEAR 2016**

Sl. No	ITEM DESCRIPTION	QTY (in M <sup>3</sup> )	Unit	Rate (in Rs.)		Amount (in Rs.)
				Fig.	Words	
1.	Maintenance dredging of inner turning basin, approaches to and alongside of berths nos.4, 8,9,10,11, breakwater and Mole berths, and mooring dolphins MD1 to MD6 areas for the years 2016 as per the scope of work given in the tender conditions. The depths varies from (-) 8.0m to (-)14.1m below Chart Datum in all types of soil as existing including loose or compacted sand, silt mixed with/without clay or soft clay or any other material including boulders, spilled cargo, broken concrete pieces/ debris metal pieces/scrap, rubber tyres, but excluding hard rock by suitable machinery/ equipment without disturbing/damaging the berthing structures and other structures including removal and covering the dredged material and dumping the same in the designated offshore dumping areas (at an approximate distance of 6 to 7 km) as shown in the drawing all as per the conditions of contract and as directed by the Engineer including all lead, lifts, cost of surveying plants, equipments, tools, labour, consumable, fuels, including mobilisation and de-mobilisation of suitable size of TSHD, etc. complete.	14,00,000	Per cum			
2.	Idle time charges for the dredgers along with all accessories, Refer clause No.26.0 of General Conditions of contract	Provisional	Per Hour /per 1000m <sup>3</sup> of TSHD	Rs 12500/-	( Rupees Twelve Thousand Five Hundred only)	
Total amount in INR(excluding service tax—refer clause 27 of GCC)						

Note: The approximate quantity to be dredged will be 1.4 cu m .

Total amount including all taxes but exclusive of service tax (Rupees -----  
-----)

Correction-----Overwriting-----Erasing-----Insertion-----

*Initials of Signatory of Tenderer*

**Date:**