

**MORMUGAO PORT TRUST**  
**ENGINEERING CIVIL DEPARTMENT**

CE/PC-783(PMC)/2016

21.07.2016

**Sub : Tender No. CE/55/2016 - Providing Signalling and Telecommunication System for Railway Network at Mormugao Port, Goa: Reply to Pre-Bid Queries.**

<b>Sr. No.</b>	<b>Tender Ref. Clause</b>	<b>Queries</b>	<b>MPT's Reply</b>
1.	b(5) Page No.1 and Clause 3 page 10.	Amount of EMD is Rs. 10,.51,100/- whereas at Clause 3 page 10 it is stated as EMD is Rs.6,82,055/- in the form of Cash, Demand Draft and Bankers Guarantee Bond.	EMD is Rs. 12,18,500/- in the form of Demand Draft drawn in the name of FA & CAO MPT payable at Vasco da Gama.
2.	6.1 Page No.11	The total completion period of the work is Nine (9) months (including monsoon) for Part 1 period completed as 7 days from the ate of receipt of acceptance letter or from the date of release of site or port whereof whichever is later. Whether Work Order will be issued before approved SIP ?	As regards to approval of SIP it is the responsibility of Port from South Western Railway. SIP will be issued alongwith the work order.
3.	iv) Appendix I Sr. No. 9 Page no.20	Minimum amount of Interim Certificate applicable till completion of works for Part I Rs. 50,000/-. This may please be reduced.	Minimum amount of Interim Certificate applicable till completion of works for Part I Rs. 30,000/-.
4a)	Appendix-II Page No.22	2) Electric power- as per the relevant rate applicable. Kindly state tentative rate.	The existing rate of Electric power is Rs.8/- per Kwh plus 20% service charges. This rate is applicable for this quarter and rate is subject to change as per the directive of Electricity Dept., Govt. of Goa every quarter.
4b)		3) Harbour Entry Permit (HEP) - as applicable. Kindly state tentative rate.	The existing rate of HEP is Rs. 10/- per day per person and is subject to change on implementation of RFID system. i.e.1 <sup>st</sup> Sept., 2016.

5.	Appendix-III Page No.23	1) Licence fees on Port Land for maintenance office buildings and other structures – rate will be charged as per scale of rates prevailing during period of contract. Kindly state the tentative rate	Existing rate for Port land at Harbour area is Rs. 541.22 per 10 sq.mtr. or part thereof per month or part thereof. In addition to this, there will be 9% pension levy and service tax as applicable. The basic rate will increase by 2% as escalation or as per the notified SOR whichever is applicable at the time of billing.
6.	xiv-1 page no. 68	1) 70% of the quoted value of items towards supply 2) 20% on installation 3) 10% against commissioning of signaling and telecommunication equipment Instead of 70% on supply 80% may be proposed. Instead of 20% on installation 10% may be proposed.	Tender condition remains unchanged.
7.	30 page no. 81	TLJB's not required as per BOQ?	Detailed specifications at Clause 30 page 81 (30.1 to 30.9) is not applicable for this work.
8.	31 page no. 81	Lifting barrier gates. Electrically operated lifting barriers given in schedule so lifting barrier gates may be removed.	Detailed specifications at Clause 31 page 81 & 82 (31.1 to 31.7) is not applicable for this work.
9.	8 page no. 2	The tenderer should submitted alongwith his tender the latest income tax clearance certificate from the Income tax authorities concerned alongwith his permanent Income Tax account no. given for assessing the income tax. Submission of ITCC has been removed in the year 2004 as per the Circular No. 2/2004 dtd. 10.2.2004. Hence this clause may please be deleted. We will submit audited balance sheet if required.	Please refer to Clause 1.2 of Detailed Tender Notice page 7 whereby Income Tax return acknowledgement is required as a documentary evidence towards filing of Income tax returns of the Company in that particular year.
10		Existing cable path diagram is to be given by MPT which indicates the exact cable path and cable depth.	Drawing of existing cable path diagram as available will be issued to successful bidder.

11		One of the tender conditions states that photo identify card for all contractor staff or his agents is mandatory and the same will be issued on payment of necessary fees as prescribed. Fees are not prescribed in the tender. The same may be prescribed.	Refer reply to Sr. No. 4(b)
12		Is there any provision for issuing form C for supply of materials against supply schedules?	Port is not issuing Form C towards supply of material.
13.		Regarding inspection of all materials, inspecting authority, RDSO/RITES /Consignee not mentioned anywhere. Same to be mentioned.	List of items with Inspection Agency will be mentioned at Annexure I.
14.		For AMC price break- up, technicians and assistant to be added suitable(one more technician and 2 more assistants to be added to issue weekly leave/leave for all staff as per statutory rules.	The requirement of technicians to be deployed at site is minimum. Tenderer may assume any extra technicians if required.
15		Execution period of 9 months will be too tight considering 2 OEMs (Distributed EI and MSDAC). These systems will be specifically manufactured to need and will therefore take considerable time for manufacturing, validating and factory acceptance test process. In addition the constraints of digging cable trenches and cable laying to be done manually. It is requested to increase completion period to 1 year.	Completion period is 9 months as stated in tender document.
16.	Item No. 1.2	A minimum financial criterion is given as Rs.3.16 crores. It is requested to enhance this limit to at least Rs. 10.00 crores.	Tender condition remains unchanged. <b>Please refer revised Minimum Eligibility Criteria.</b>
17		Tender documents submission date to be extended by 2 weeks	Tender condition remains unchanged. <b>The last date of submission of Tender document is 10.08.2016 upto 15.00 hrs.</b>

18.		What is the distance between the extreme most point at dead end and main EI room	Distance between extreme most point at dead end and main EI room is 800 mtrs. <b>Tenderers may please note that these extreme end points towards western side are not covered under interlocking and machine operated. They will be operated on manually hand lever points.</b>
19		What types of S&C are used in the yard (conventional or thick web)	S&C used in the yard will be conventional.
20		Is the LC gate shown at dead end side of yard required to be interlocked?	No.
21	Supply item no. 22 of BOQ	Is it necessary to use 30 core cables, instead 12 and 18 core cables can be used.	<b>Please refer to revised Bill of Quantities.</b>
22		Power cable is not included in BOQ Will it be provided by MPT?	<b>Please refer to revised Bill of Quantities.</b>
23		For track crossing, GI/RCC pipe is mentioned. Will DWC pipes be acceptable? (Qty. of 200 mtrs. is on lower side).	<b>Please refer to revised Bill of Quantities.</b>
24		BOQ does not include Axle counter verification locations for resetting process.	Item specification for MSDAC is including AXLE Counter verification location for resetting process.
25		When will the crank be placed? In SM's office or in locations.	Crank will be placed in SM's Office and also in location box.

**CHIEF ENGINEER**