

MORMUGAO PORT TRUST
ENGINEERING MECHANICAL DEPARTMENT

NOTICE INVITING BUDGETORY OFFERS

Name of Work	NAME OF WORK "Laying Underground L.T. Aluminium armoured cable in Headland area at MPT"
Date of submission of budgetary quotation	On or Before 26 /09/2016 at 1500 Hrs.
Address for communication:	Executive Engineer(E-HL), Mechanical Engineering Department, Mormugao Port Trust, Electrical Section, 1st Floor, Admin. Building, Headland sada Vasco-de-Gama Goa - 403804
Contact Details	Phone : (0832) 2594241 Email : trevor,silveira@mptgoa.com
Website	www.mptgoa.com

CHIEF MECHANICAL ENGINEER
MORMUGAO PORT TRUST

1. SCOPE OF WORK:-

- 1.1 Laying underground L.T. Aluminum armoured cable in Headland area of size 4 Core 35 sq mm and 3.5 Core 95 sq mm in trench of depth 60cms, width 40cms. Including supply and laying of bricks. After laying, the cable trench should be back filled with soil. (The cable will be supplied by the Port.)
- 1.2 Laying underground L.T. Aluminum armoured cable in Headland area of size from 4 Core 35 sq mm and 3.5 Core 95 sq mm cable through GI pipe by cutting the road. The road to be made good after laying the cable. (Cable and Pipe will be supplied by the Port)
- 1.3 Clamping the L.T. Aluminium armoured cable of size 4 Core 35 sq mm and 3.5 Core 95 sq mm. on the wall with necessary clamps.
- 1.4 Terminating the Aluminium armoured cable of size 4 Core 35 sq mm and 3.5 Core 95 sq mm. with necessary lugs and glands.

PRICE SCHEDULE (BILL OF QUANTITIES)

NAME OF WORK: **Laying Underground Aluminium armoured cable in Headland area at MPT**

Sr. No.	Description	Qty	Unit	Rate / Unit in (Rs.)		Amount (Rs)
				In figure	In words	
1	Laying underground L.T. aluminium armoured cable of size 4 core 35 sqmm, Excavation upto depth of 60cm and width of 40cm. Including supply and laying of bricks and refilling back with soil. (Cable will be supplied by Port)	300	mtr			
2	Laying underground L.T. aluminium armoured cable of size 3.5 core 95 sqmm, Excavation upto depth of 60cm and width of 40cm. Including supply and laying of bricks and refilling back with soil. (Cable will be supplied by Port)	100	Month			
3	Laying underground L.T. Aluminium armoured cable in Headland area of size from 4 Core 35 sq mm and 3.5 Core 95 sq mm cable through GI pipe by cutting the road to depth of 60 cms. The road to be made good after laying the cable. (Cable and Pipe will be supplied by the Port) 1)4Cx 35sq mm 2)3.5C x 95 sq mm	10 05	Mtr Mtr			
4	Clamping L.T. Aluminium armoured cable of size 4 Core 35 sq mm and 3.5 Core 95 sq mm. on the wall with necessary clamps. 1)4Cx 35sq mm 2)3.5C x 95 sq mm	10 10	Mtr Mtr			
5	Terminating L.T. Aluminium armoured cable of size 1)4 Core 35 sq mm 2) 3.5 Core 95 sq mm. With necessary lugs and glands.	4 2	Nos Nos			

--	--	--	--	--	--	--

(Rupees _____ only)

Note: The rates shall be inclusive of all taxes and duties except service tax which will be paid extra as applicable. However, if new tax is imposed by Central/State Government, the same will be reimbursed on submission of documentary evidence.