

MORMUGAO PORT TRUST
ENGINEERING MECHANICAL DEPARTMENT

NOTICE INVITING BUDGETORY OFFERS

Name of Work	" Dismantling and shifting of High mast from MOHP area"
Date of submission of offers	on or before 30/01/2017 at 1430 Hrs.
Address for communication:	SE(E-H) Engineering Mechanical Dept., Mormugao Port Trust, Power House, Baina Workshop, Mormugao, Goa – 403802.
Contact Details	Phone :0832-2594515/ 2594579 Email : cme.mgpt@gmail.com , melchior_teles@yahoo.co.in , soaresfreddy@gmail.com
Website	www.mptgoa.com

CHIEF MECHANICAL ENGINEER
MORMUGAO PORT TRUST

Dismantling and shifting of High mast from MOHP area

1.1. GENERAL

Mormugao Port Trust, Goa, wants to remove 13 no's of High mast from MOHP area, which includes 9 no's High mast of 30 meters height and 4 no's High mast of height 40 meters. .

1.2 Scope of work:

The scope of work broadly includes:

1. Lowering of lantern carriage and removal of the fittings, chokes, wiring including trailing cable of **30mtrs** height High mast: HM5, HM6, HM7, HM8, HM9, HM10, HM11, HM12 and HM 20.
2. Lowering of lantern carriage and removal of the fittings chokes, wiring including trailing cable of **40mtrs** height high mast: HM16, HM17, HM18 and HM19.
3. Loosening of foundation bolts and lowering the high mast down using the suitable crane. (Crane will be provided by The Port)
4. Removal of the lantern carriage.
5. Removal of the motors, pulleys, wire ropes, gearbox, Electrical switchgear and associated hardware and handing over to Port Engineer.
6. Separation of high mast telescopic sections into 3 sections. Identification of each telescopic section of each High Mast with suitable paint so that the same can be reused whenever necessary
7. Category wise .segregation of all items of each High Mast
8. Removal of the high mast supply panel/JB carefully without damaging its structure and internal components. (Disconnection of main supply cable will be done by the port).
9. Transportation of removed high mast along with its associated components to MM and storing at designated location.

Dismantling and shifting of High mast from MOHP area

BILL OF QUANTITIES

SR.NO	DESCRIPTION	QUANTITY	RATE	AMOUNT
1	Lowering and removing of lantern carriage motors, pulleys, wire ropes, gearbox, electrical switchgear and associated hardware of High mast such as the fittings, chokes, and trailing cable of 30mtrs height high mast: HM5, HM6, HM7, HM8, HM9, HM10, HM11, HM12, HM 20 and HM16, HM17, HM18, HM19, of 40 Mtrs height	13 no's		
2	Loosening of foundation bolts and lowering the high mast down using the suitable crane (Crane will be supplied by Port.)	13 no's		
3	Separation of high mast telescopic sections into 3 sections. Identification of each telescopic section of each High Mast with suitable paint so that the same can be reused whenever necessary	LS		
4	Removal of the high mast supply panel/JB and internal components. (Disconnection of main supply cable will be done by the port).	13		
5	Transportation of removed high mast along with its associated components to MM and storing at Designated location.	LS		
		TOTAL		

(In words Rupees _____
_____)

Note: The offered rates shall be inclusive of all taxes except Service Tax which will have to be paid/ reimbursed by MPT as applicable. However, any new tax will be imposed by State/Central Govt. and same will be reimbursed on producing documentary proof.